

TOWN OF WILLIAMSTOWN  
REQUEST FOR RECLAIMING AND ADDING MATERIALS  
TO EXISTING SURFACE BIDS

The Town of Williamstown is request sealed bids for projects within the 2022 summer/fall road project season.

Project Description:

This project consists of reclaiming 12-inch depth of Falls Bridge Road from the intersection of Route 14 to the Barre Town Line and add ¾" or 1 ½" clean crushed stone with a wear less than 40% per ASTM C-131 then compact surface using static effort to meet a minimum 95% of ASTM D 1557-12 (Modified Proctor) Static compaction will prevent excessive vibrator amplitude that might disturb the lower sub-grade soil and create wash boarding. Level final grade (crown) before paving so that the surface water can drain to drainage trenches on each edge of the road; final compaction should meet 95% of ASTM D1557 -12 (Modified Proctor). Work must be completed by October 31, 2022.

Pre-Bid Site Visit:

A Pre-Bid site visit for the Town of Williamstown Falls Bridge Road project will be held on July 14, 2022, at 3:00 p.m. Bidders will meet at the Williamstown Town Office 2470 VT Rte. 14.

Instructions to Bidders:

All sealed bids must be submitted by July 28, 2022, at 4:00 p.m. to:  
Williamstown Town Manager  
P.O. Box 646  
2470 Vermont Route 14  
Williamstown, VT 05679

Disclaimer:

The Town of Williamstown reserves the right:

- a. To accept or reject any and all bids.
- b. To amend, modify, or withdraw this Request for Bids.
- c. To cancel any and/or all projects prior to the start of construction without prior notification.